

QUOTATION SCHEDULE

KERALA STATE FILM DEVELOPMENT CORPORATION Ltd, THIRUVANATHAPURAM.

Name of Work : Renovation of Kairali /Sree theatre complex at Calicut. (Assembly building, internal works only in theaters hall)

L. No	Description	Qty	Unit	Rate					Amount Rs. Ps A x F
				Rate (cost index of Calicut 31.06% (WEF 15.03-2019) added to DSR 2016 (B)	CGST- 9% (C)	SGST- 9% (D)	Flood Cess 1% (E)	Total rate F = (B+C+D+E)	
1	Supply, installation, testing and commissioning of Fire alarm Control Panel with Talk back Unit of 8 Zone complete with charger, rectifier, alarm display with all other necessary attachments . Make: Agni/Equivalent	1	Nos.						-
2	Supply, installation, testing and commissioning of manual call points with talk back unit. Make: Agni/Equivalent	7	Nos						-
3	Supply, installation, testing and commissioning of audio alarm hooters. Make: Agni/Equivalent	7	Nos.						-
4	Supply, installation, testing and commissioning of conventional optical/Heat smoke detector with base. Make-APPOLO/SYSTEM SENSOR/Siemens	35	Nos.						-
5	Supply, laying, testing and commissioning of 2 Core x 1.5 Sq.mm cable, Armoured Screened FRLS Twin Twisted PVC Insulated copper cable ISI along with all accessories required for complete installation, making terminations etc where required Make : Havells, Finolux/Polycab/Universal/orbit	600	Mtrs						-
Total									Rs.


Theatre Manager

Name and address of Contractor

Terms and conditions:

1. The rate shall be hold firm for a period of six months. Minimum one year warranty may be provided.
2. Quotation shall be submitted on plain paper showing specifications, quoted price should be inclusive of all taxes and rates.
3. 5% of the total order value will be retained as Security Deposit till the expiry of warranty period.
4. The successful quotationer has to execute an agreement for supply of items with KSFDC on receipt of work order.
5. Managing Director, KSFDC reserves' the right to reject any or all quotations without assigning any reason whatsoever.
6. The decision of KSFDC in accepting the quotation will be final. Tenderers may enclose a list of their installations in Kerala.
7. Last date of receipt of quotations will be 3 pm on 31-01-2020 The quotations will be opened on the same day at 3.30pm in the presence of available quotationers.
8. A copy of quotation notice shall be enclosed with the quote duly signed for acceptance of the terms.
9. Completion period of the work shall be Two weeks from the date of of work order

Name and address of Contractor


Theatre Manager